

## Leach Residue Storage Facility Closure Plan at Henty Gold Mine Western Tasmania



1. Plan for closure rehabilitation before pond used for storage of leach residue is built



2. Use landform materials recovered during this and other construction projects on site
3. Criteria for landform
  - a. safe, stable, non-erodable
  - b. natural, visually pleasing lines
  - c. vegetative cover to conform with natural landscape
  - d. low to zero maintenance over the long term



4. Input from experts on revegetation, seed and species selection
5. Peat cover and revegetation of access roads



6. Ongoing monitoring via
  - a. piezometers
  - b. runoff sampling
  - c. groundwater bore sampling
  - d. seepage sampling
  - e. photographic viewpoint reviews